

Millbrook – Ground Investigation Factual Summary

Sofie Lindqvist · 24 February 2026 · MB-GEO-RPT-0001

Scope

24 trial pits, 6 window sample boreholes, 18 pile pull-out tests and 12 electrical resistivity tests across the 142 ha site, carried out 12–23 January 2026.

Findings

- Topsoil 0.25–0.40 m over firm to stiff sandy clay (boulder clay) – suitable for driven steel tracker piles.
- Groundwater encountered at 1.6–2.4 m in the southern fields near the stream; seasonal monitoring started.
- Pull-out capacity of C-section piles at 1.8 m embedment: 18–31 kN (design requirement 15 kN).
- Soil resistivity 45–120 $\Omega \cdot m$ – earthing design at the substation can follow the standard approach.
- No contamination found; former farm yard area to be checked during construction (watching brief).

Next steps

Results shared with SunForge EPC for their tender design. A supplementary investigation at the BESS compound is planned after the planning decision (expected Q1 2027).