

Glenmore Onshore Wind – Technical Due Diligence

Acquisition of a 48 MW consented project, Scottish Highlands

Sofie Lindqvist · 24 July 2026 · WE-ENG-RPT-0031

1. Executive summary

Weyland is considering the acquisition of the Glenmore Onshore Wind project (48 MW, consented 2025) from its developer. Engineering carried out a desktop technical due diligence between 8 June and 17 July 2026 with a site visit on 1 July. Overall, the project is technically sound. We identified **two red flags** and five amber items, which should be reflected in the purchase price or in conditions precedent.

Rating	Count	Topics
Red	2	Energy yield overstated; grid connection date at risk
Amber	5	Turbine tip height vs. consent, access route, peat, ice throw, met data length
Green	11	Consent conditions, land rights, layout, noise, shadow flicker, ...

2. Project description

- Location: Glenmore estate, 380–470 m elevation, 9 km from the nearest trunk road.
- Consent: 8 turbines, maximum tip height 200 m, granted April 2025, valid for five years.
- Proposed turbine: 6.0 MW class, 162 m rotor, 119 m hub height.
- Grid: 132 kV connection offer at Glenmore Grid Supply Point, connection date Q4 2029.

3. Red flags

3.1 Energy yield

The vendor's energy yield assessment states a net P50 of 158 GWh/a (capacity factor 37.6 %). Our review finds it overstated by 6–8 %: the met mast record is only 11 months long, the long-term correction uses a reference with poor correlation ($R^2 = 0.71$), and wake losses of 4.1 % are low for the tight layout (3.2D crosswind spacing). Our re-assessment gives a net P50 of **147 GWh/a** and a 10-year P90 of 131 GWh/a.

3.2 Grid connection

The connection date depends on reinforcement of the 132 kV circuit by the transmission owner, which is currently in the queue behind three larger projects. Our Grid Connection Specialist Ahmed Rahimi rates the risk of a delay to 2031 as high.

4. Amber items

#	Topic	Finding	Recommendation
---	-------	---------	----------------

A1	Tip height	6 MW candidate turbines at 200 m tip leave no margin	Confirm turbine shortlist before SPA
A2	Access	Two bridges on the access route need strengthening	Budget EUR 1.4 m
A3	Peat	Peat depth up to 2.8 m at T5 and T6	Peat management plan, micro-siting
A4	Ice throw	Public path within 1.5 × tip height of T2	Ice detection and automatic stop
A5	Met data	Only one mast, 11 months	Install LiDAR now for 12 months before FID

5. Lessons applied from Kestrel Ridge

Our Kestrel Ridge experience (similar elevation, T-07 gearbox failure in January 2026, incident KR-INC-2026-003) suggests budgeting for cold-climate packages and a stock of critical spares in Scotland.

6. Conclusion

Engineering supports proceeding to binding offer **only** with a price adjustment reflecting the lower P50 and with a condition precedent on the grid reinforcement timetable. See IC paper in Project Pipeline & Bids.

Prepared by Sofie Lindqvist with Mei Tanaka (electrical), Oliver Grant (civil/geotech) and Ahmed Rahimi (grid).