

Harrow Bay Offshore Wind

Project fact sheet · August 2026

Noah Fischer · 20 August 2026



Capacity	480 MW
Location	UK North Sea, 38 km off the coast of Harrow Bay
Turbines	40 × Halden HTS-12 (12 MW), rotor diameter 236 m, hub height 140 m
Foundations	Monopiles, 9.5 m diameter, water depth 28–36 m
Export	2 × 220 kV export cables, 62 km each, to onshore substation Harrow Bay East
Array cables	66 kV array cables, ~ 95 km total
Investment	EUR 1,620 million (EUR 1.1 bn project finance)
Annual generation	~ 1.9 TWh – the equivalent of 520,000 homes
Offtake	150 MW to Arcturus Steel under a 15-year PPA

Timeline

Date	Milestone
2023-11-20	Development consent granted
2025-06-30	Turbine supply agreement signed with Halden Turbine Systems
2026-02-12	Final investment decision (FID) and financial close
2026-04-07	Offshore construction start – first monopile installed

2026-08-19	Offshore substation topside installed
2026-10-02	Status: 14 of 40 monopiles installed
2027-03-01	Planned: first turbine installation
2027-09-30	Planned: first power
2028-06-30	Planned: commercial operation date (COD)

Environment

Seabird and harbour porpoise monitoring by Marlow Ecology; noise mitigation with bubble curtains during piling; piling paused during seasonal restrictions.

Media contact: Noah Fischer, Marketing & Communications Manager · press@weyland-energy.example · +49 40 3290 4410